



SHREEJI ASSOCIATES

CHARTERED ENGINEER & COMPETENT PERSON

CERTIFICATE OF STABILITY

Certificate No :- SPC/01

Date: 20/03/2022

1. Name of the School : M/S. SINGHANIA PUBLIC SCHOOL
(C/O J.K.PAPER LTD)
2. Village town & district which the School is situated : P.O : Central Pulp Mill , Fort : Songadh ,
Dist : Tapi , Gujarat
3. Full postal address of the School : P.O : Central Pulp Mill , Fort : Songadh ,
Dist : Tapi , Gujarat
4. Name of the Occupier of the School : MR. MUKUL VERMA (PRESIDENT)
5. Nature of process to be Occur. : School (Education Foundation)
6. Number of floors . : Ground + 2 Floor.

Remark : Instructions for protection of structure must be followed as per annexure attached with this certificate.

I certify that I have inspected the above said premises & the drawing provided by M/S. SINGHANIA PUBLIC SCHOOL (C/O J.K.PAPER LTD) and examined various structure Members. I am of the opinion that all the works of M/S. SINGHANIA PUBLIC SCHOOL(C/O J.K.PAPER LTD) construction in the premises is structurally sound & that its stability will not be endangered by its use as a School (Education Foundation.)

Signature: BDBhavsar
Bharat D. Bhavsar
Chartered Engineer & Competent Person
B.E. (Civil), A.M.I.E., L.L.B.,

Number & Date of the Competency Certificate : GUJ/DISH/CPT/A/0209/2014
Dated: 02/07/2021
Issued by : Director, Industrial Safety & Health
Gujarat State, Ahmedabad.



NEXT TEST DUE ON :- 19/03/2027



SHREEJI ASSOCIATES

ANNEXURE

Ref. Stability Certificate No.: SPC/01

Date : - 20/03/2022

INSTRUCTIONS ATTACHED TO THE CERTIFICATE OF STABILITY

- 1) The structure shall be maintained in good working condition ,shall be regularly inspected & any small crack, bending ,tilting, leaning or any change appearance in the structure fabrication shall be immediately informed to the respective authority for right assessment, decision & suggestion for maintenance of safe structure.
- 2) Cement sheet protection cover should be given to all RCC Slab and beams where direct heat/chemical vapor/steam/ are coming in direct contact
- 3) Existing condition of machine, load & vibration shall be maintained. Any excess or increase shall be informed to respective authority for verification, assessment & decision.
- 4) Any spillage, Gas leakage, exposures or any abnormal impact or other side effect shall be reported to respective authority for result, deviation & precaution for stability.
- 5) All structure members shall be protected from acidic materials, salinity. Arrangement of acidic effluent drainage shall be maintained properly.
- 6) Water deposited at plinth level nearby to RCC or steel column and on terrace floor level shall be avoided.
- 7) Any construction or part of it which has not been approved in plan is not involved in this certificate.
- 8) Any structure or part of it approved in plan but not constructed yet the day of inspection is not involved in this certificate.

Signature: BDBhavsar
Bharat D. Bhavsar
Chartered Engineer & Competent Person
B.E. (Civil), A.M.I.E., L.L.B.

Number & Date of the
Competency Certificate
Issued by

GUJ/DISH/CPT/A/0209/2014
Dated: - 02/07/2021
Director, Industrial Safety & Health
Gujarat State, Ahmedabad

